

230500S01 Common Work Results for HVAC

1. Do not provide any devices containing mercury unless there is not a mercury free device on the market, which will perform the same function.
2. No plastic pipe is to be used inside any building or structure unless justified and written approval is received from University's assigned Project Manager. The project program may authorize the use of plastic pipe.
3. Pipe joints shall use a joint material selected to minimize the potential for contamination. For example, to minimize lead contamination in copper tubing select 95/5 tin/antimony solder.